



CHEMISTRY BUILDING ROOM 123 - AUTOCLAVE REPLACEMENT

PPA NO. 24-1115 MONTANA STATE UNIVERSITY
BOZEMAN, MONTANA ISSUED FOR BID 07-02-2025



1 CAMPUS VICINITY MAP - LOCATION OF CHEMISTRY BUILDING
NOT TO SCALE




PENTHOUSE

NOTE: PROVIDE AND INSTALL NEW RATED METAL ACCESS DOOR INTO EXISTING CHASE WALL USING LEAST IMPACTFUL MEANS AND METHODS POSSIBLE. IT IS BELIEVED THAT EXISTING WALL IS FRAMED WITH 3/8" SHIRT WALL STUDS AT 16" OC. LOCATE NEW ROUGH OPENING 10" ABOVE FINISHED FLOOR. CUT ONE INTERMEDIATE WALL STUD, AND TRIM OPENING WITH NEW METAL TRACKS TOP AND BOTTOM. PROVIDE A DOOR FRAME ASSEMBLY SIMILAR TO EXISTING DOORS ON FIRST AND SECOND STORIES. PATCH AND REPAIR FINISHED WALL SURFACE AS REQUIRED.


SIZE: 30" WIDE X 30" HIGH
RATING: 1-1/2 HOURS
FINISH: FACTORY (PRE-FINISHED)
ORIENTATION: LEFT HAND REVERSE

ACCEPTABLE MANUFACTURERS INCLUDE, BUT ARE NOT LIMITED TO, KARP ASSOCIATES, INC. AND BEST ACCESS DOORS.




SECOND LEVEL

THIRD LEVEL



LOWER LEVEL



MAIN LEVEL

2 BUILDING KEY PLANS - ALL LEVELS
SCALE: 1" = 30'

PROJECT SEQUENCING REQUIREMENTS

- WORK NOT AFFECTING EXISTING AUTOCLAVE USE AND OPERATION CAN BE PERFORMED AT ANY TIME BETWEEN "NOTICE TO PROCEED" AND "SUBSTANTIAL COMPLETION" DATES INDICATED IN THE PROJECT MANUAL, WITHIN OTHER CONSTRAINTS INDICATED HEREIN.
- EXISTING AUTOCLAVES TO BE LEFT IN PLACE AND FUNCTIONAL AS LONG AS POSSIBLE. DEMOLITION TO START NO EARLIER THAN MAY 15, 2026 AND NO EARLIER THAN ONE MONTH BEFORE NEW AUTOCLAVES WILL BE ON SITE.
- NEW AUTOCLAVES MUST BE INSTALLED AND FUNCTIONAL BEFORE SEPTEMBER 4, 2026.
- REMAINDER OF WORK (WALL MODIFICATIONS, FINISHES, ETC.) TO BE COMPLETED BY THE DATE INDICATED IN THE PROJECT MANUAL.
- OUTAGE FOR NEW CONNECTION TO STEAM PIPING MAIN IN PENTHOUSE TO OCCUR DURING WARM WEATHER WHEN AIR HANDLING UNITS DO NOT REQUIRE HEATING (ABOVE 45°F).
- ELECTRICAL OUTAGES (FOR OTHER THAN AUTOCLAVE SYSTEMS) TO BE COORDINATED WITH OWNER. THIS MAY REQUIRE SCHEDULING DURING A BREAK WHEN CLASSES ARE NOT IN SESSION OR OTHER TIME TO MINIMIZE IMPACT ON OCCUPANTS.

GENERAL NOTES - PROJECT:

- ALL CONSTRUCTION AND CONSTRUCTION METHODS TO BE IN ACCORDANCE WITH APPLICABLE CODES, GOVERNMENTAL AGENCIES, AND LOCAL DESIGN CRITERIA, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - INTERNATIONAL EXISTING BUILDING CODE, 2021 EDITION
 - ICC A117.1 - ACCESSIBILITY, 2017 EDITION
 - INTERNATIONAL ENERGY CONSERVATION CODE, 2021 EDITION (PENDING COMCHECK)
 - INTERNATIONAL FIRE CODE, 2021 EDITION
 - INTERNATIONAL MECHANICAL CODE, 2021 EDITION
 - UNIFORM PLUMBING CODE, 2021 EDITION
 - INTERNATIONAL FUEL GAS CODE, 2021 EDITION
 - NATIONAL ELECTRICAL CODE, 2020 EDITION
- ANY AMBIGUITIES OR DISCREPANCIES DISCOVERED BY THE USE OF THESE DRAWINGS SHALL BE REPORTED TO THE ARCHITECT IMMEDIATELY.
- CHANGES OR DEVIATIONS FROM THE CONTRACT DOCUMENTS MADE WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT ARE UNAUTHORIZED. COORDINATE NECESSARY MODIFICATIONS WITH THE ARCHITECT PRIOR TO CONSTRUCTION.
- IN THIS ARCHITECTURAL PLAN SET, WALL DIMENSIONS ARE TYPICALLY TO THE FACE OF CONCRETE, FACE OF MASONRY, OR FACE OF FRAMING. COLUMN, PIER, AND DOOR AND WINDOW DIMENSIONS ARE TYPICALLY TO THE CENTERLINE OF THE ELEMENT OR UNIT. GENERAL CONTRACTOR TO VERIFY DIMENSIONS PRIOR TO CONSTRUCTION AND NOTIFY ARCHITECT OF ANY DISCREPANCIES.
- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SAFETY AND SHALL TAKE WHATEVER MEASURES ARE NECESSARY TO ENSURE THE HEALTH AND SAFETY OF THEIR EMPLOYEES, SUBCONTRACTORS, BUILDING OCCUPANTS, PEDESTRIANS NEAR THE CONSTRUCTION SITE AND ACCESS ROUTES, AND ALL OTHER PERSONS IN AREAS AFFECTED BY THE CONTRACTOR'S CONSTRUCTION ACTIVITIES. REFER TO THE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- THE CONTRACTOR SHALL PAY PARTICULAR ATTENTION TO SAFETY WHILE WORKING NEAR BUILDING ENTRANCES / EXITS. UNLESS DIRECTED OTHERWISE, ALL BUILDING ENTRANCES / EXITS ARE TO REMAIN OPEN AND ACCESSIBLE TO BUILDING OCCUPANTS DURING THE COURSE OF THE PROJECT. SPECIAL PROTECTION MEASURES MAY BE REQUIRED.
- THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION AND SCHEDULING OF ALL REQUIRED INSPECTIONS DURING THE COURSE OF THE CONSTRUCTION PROJECT. PARTIES REQUIRED TO ATTEND SHOULD BE GIVEN A MINIMUM OF TWO WORKING DAYS NOTICE.
- CONTRACTOR TO COORDINATE ALL MECHANICAL, ELECTRICAL, FIRE SUPPRESSION, FIRE ALARM, COMMUNICATIONS, AND OTHER UTILITY SHUT-DOWNS, AS WELL AS PUBLIC PATHWAY CLOSURES, WITH MSU PROJECT MANAGER AT LEAST 5 CALENDAR DAYS IN ADVANCE, PER MSU REQUIREMENTS.

GENERAL NOTES - CONSTRUCTION:

- CONTRACTOR TO COMPLETE ALL CONSTRUCTION WORK IN A MANNER THAT MAINTAINS THE INTEGRITY OF ALL FIRE-RATED AND SMOKE-RATED ASSEMBLIES.
- CONTRACTOR TO PROVIDE SOLID BLOCKING AS REQUIRED FOR THE ATTACHMENT OF ALL CASEWORK, MILLWORK, EQUIPMENT, TOILET PARTITIONS, AND SIMILAR INSTALLATIONS.

GENERAL NOTES - SITE / STAGING:

- THE CONTRACTOR SHALL MINIMIZE INTERFERENCE WITH ADJOINING STREETS, SIDEWALKS, PARKING AREAS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES DURING CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL NOT BLOCK STREETS, SIDEWALKS, OR ACCESS TO DUMPER LOCATIONS AT ANY TIME.
- THE CONTRACTOR SHALL PROTECT EXISTING SITE IMPROVEMENTS AND LANDSCAPING FROM DAMAGE CAUSED BY CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL RESTORE EXISTING SITE IMPROVEMENTS AND LANDSCAPING DAMAGED BY CONSTRUCTION OPERATIONS AS DIRECTED BY THE ARCHITECT PRIOR TO SUBSTANTIAL COMPLETION.
- THE CONTRACTOR SHALL PROTECT EXISTING BUILDINGS FROM DAMAGE, CONTAMINATION, AND SOILING CAUSED BY CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL KEEP BUILDING ENTRANCES, CORRIDORS, AND STAIRWELLS CLEAR OF CONSTRUCTION MATERIALS, TOOLS, AND EQUIPMENT AT ALL TIMES. THE CONTRACTOR SHALL RESTORE EXISTING BUILDINGS DAMAGED BY CONSTRUCTION OPERATIONS AS DIRECTED BY THE ARCHITECT PRIOR TO SUBSTANTIAL COMPLETION.

ABBREVIATIONS

THE FOLLOWING ARE GENERAL ABBREVIATIONS THAT MAY BE FOUND IN THE DRAWING SET. REFER TO VARIOUS SCHEDULES FOR ADDITIONAL ABBREVIATIONS THAT MAY BE FOUND IN THE SCHEDULES.

AB	= ANCHOR BOLT	JAN	= JANITOR
ABV	= ABOVE	LAM	= LAMINATE
ADD	= ADDENDUM	LAV	= LAVATORY
ADJ	= ADJACENT	MAX	= MAXIMUM
AFF	= ABOVE FINISHED FLOOR	MECH	= MECHANICAL
ALT	= ALTERNATE	MFR	= MANUFACTURER
		MIN	= MINIMUM
BLKG	= BLOCKING	MISC	= MISCELLANEOUS
BOB	= BOTTOM OF BEAM	MS	= MANUFACTURER'S STANDARD
BOB	= BASIS OF DESIGN		
BRG	= BEARING		
		NIC	= NOT IN CONTRACT
CAB	= CABINET		
CJ	= CONTROL JOINT		
CLR	= CLEAR	OC	= ON CENTER
CMU	= CONCRETE MASONRY UNIT	OD	= OUTSIDE DIAMETER
COMP	= COMPOSITE	OH	= OVERHEAD
CONC	= CONCRETE	OSB	= ORIENTED STRAND BOARD
CONT	= CONTINUOUS		
CPT	= CARPET	PEMB	= PRE-ENGINEERED METAL BUILDING
		PL	= PLATE
DEMO	= DEMOLITION	PVC	= POLYVINYLCHLORIDE
DF	= DRINKING FOUNTAIN		
DIA	= DIAMETER	R	= RISER
DF	= DRINKING FOUNTAIN	RAD	= RADIUS
		REQD	= REQUIRED
		RO	= ROUGH OPENING
EIFS	= EXTERIOR INSULATION AND FINISH SYSTEM	SCHED	= SCHEDULE
		SF	= SQUARE FEET
EL	= ELEVATION	SM	= SIMILAR
ELEC	= ELECTRICAL	SPECS	= SPECIFICATIONS
EPS	= EXPANDED POLYSTYRENE		
ETR	= EXISTING TO REMAIN	T	= TREAD
EW	= EACH WAY	T&G	= TONGUE AND GROOVE
FD	= FLOOR DRAIN	TOB	= TOP OF BEAM
FDN	= FOUNDATION	TOC	= TOP OF CONCRETE
FE	= FIRE EXTINGUISHER	TOD	= TOP OF DECKING
FF	= FINISH FLOOR	TOF	= TOP OF FOOTING
FLR	= FLOOR	TOPL	= TOP OF PLATE
FS	= FLOOR SINK	TOPR	= TOP OF PIER
FV	= FIELD VERIFY	TOS	= TOP OF STEEL
		TOSL	= TOP OF SLAB
GB	= GYPSUM BOARD	TP	= TYPICAL
GC	= GENERAL CONTRACTOR		
		UNO	= UNLESS NOTED OTHERWISE
HC	= HANDICAPPED, ACCESSIBLE	VB	= VAPOR BARRIER
HOR	= HORIZONTAL	VERT	= VERTICAL
HR	= HOUR		
HVAC	= HEATING / VENTILATING / AIR CONDITIONING	WC	= WATER CLOSET
		WWF	= WELDED WIRE FABRIC
ID	= INSIDE DIAMETER	XPS	= EXTRUDED POLYSTYRENE
INSUL	= INSULATION		

INDEX OF DRAWING SHEETS		
SHEET	SHEET TITLE	DATE
		ISSUED FOR BID - 02 JUL 25
CVR	COVER, PROJECT NOTES, INDEX OF DRAWING SHEETS	
A1	FLOOR PLANS, DETAILS	
M0.1	MECHANICAL LEGENDS AND SCHEDULES	
M1.1	MAIN FLOOR HVAC AND PIPING PLAN	
M2.0	ENLARGED PIPING PLANS	
M2.1	ENLARGED AUTOCLAVE PLANS	
M3.0	PENTHOUSE HVAC AND PIPING PLAN	
M3.0	MECHANICAL DETAILS	
M4.1	MECHANICAL DETAILS	
E0.1	ELECTRICAL LEGENDS AND SCHEDULES	
E1.1	ENLARGED ELECTRICAL PLAN	



MSU-CPDC


MONTANA STATE UNIVERSITY
BOZEMAN, MONTANA
PHONE: 406.994.5413
FAX: 406.994.5665

CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT
BOZEMAN, MONTANA



DRAWN BY: SS, AC, MV
REVIEWED BY: SS, AC, MV

REV. DESCRIPTION DATE



PPA # 24-1115

A/E # ...

A118 24-025

SHEET TITLE

SHEET
CVR

DATE
IFB 07-02-2025



3 ACCESS DOOR
NOT TO SCALE



2A EXISTING AUTOCLAVES (FRONT)
NOT TO SCALE




2B EXISTING AUTOCLAVES (REAR)
SCALE: 1:10.50

GENERAL NOTES - DEMOLITION


- PROTECT EXISTING CONSTRUCTION TO REMAIN. REFER TO DIVISION 2 SECTION SELECTIVE DEMOLITION FOR ADDITIONAL INFORMATION.
- THE FOLLOWING DEFINITIONS PERTAIN TO DEMOLITION WORK:
- REMOVE: DETACH ITEMS FROM EXISTING CONSTRUCTION AND LEGALLY DISPOSE OF OFF-SITE UNLESS INDICATED TO BE REMOVED AND SALVAGED OR REMOVED AND REINSTALLED.
- REMOVE AND SALVAGE: DETACH ITEMS FROM EXISTING CONSTRUCTION, IN A MANNER TO PREVENT DAMAGE, AND DELIVER TO OWNER AS INDICATED.
- REMOVE AND REINSTALL: DETACH ITEMS FROM EXISTING CONSTRUCTION, IN A MANNER TO PREVENT DAMAGE; PREPARE FOR REUSE, AND REINSTALL WHERE INDICATED.
- EXISTING TO REMAIN: EXISTING ITEMS OF CONSTRUCTION THAT ARE NOT TO BE REMOVED.

KEY NOTES - DEMOLITION

- REMOVE EXISTING AUTOCLAVE APPLIANCES COMPLETELY. REFER TO ENGINEERING PLANS FOR ADDITIONAL INFORMATION.
- EXISTING OVERHEAD SOFFIT TO REMAIN - PATCH AND REPAIR AS REQUIRED.
- RENOVATE EXISTING PARTITION AS REQUIRED FOR INSTALLATION OF NEW AUTOCLAVES - REFER TO NEW CONSTRUCTION PLANS FOR ADDITIONAL INFORMATION.
- EXISTING FLOOR SINK TO REMAIN.




1 MAIN LEVEL FLOOR PLAN - DEMOLITION
SCALE: 1/8" = 1'-0"



8 AUTOCLAVE ENLARGED ELEVATIONS
SCALE: 1/2" = 1'-0"

NOTE: THE AUTOCLAVES REPRESENTED IN THIS DETAIL ARE FROM PRIMUS (BASIS OF DESIGN).




6 WALL BETWEEN ROOMS 121 AND 123
SCALE: 1/4" = 1'-0"


NOTE: THE CONDITIONS REPRESENTED IN THIS DETAIL ARE FOR PRIMUS EQUIP. (BASIS OF DESIGN)

GENERAL NOTES - NEW CONSTRUCTION


- PROTECT EXISTING CONSTRUCTION TO REMAIN. REFER TO DIVISION 2 SECTION SELECTIVE DEMOLITION FOR ADDITIONAL INFORMATION.
 - REFER TO MECHANICAL FOR ADDITIONAL INFORMATION PERTAINING TO INSTALLATION OF NEW STEAM SERVICE COMING FROM PENTHOUSE ABOVE.
- KEY NOTES - NEW CONSTRUCTION**
- RENOVATED OR NEW PARTITION - LOCATION, CONSTRUCTION, AND FINISH TO MATCH EXISTING.
 - VERIFY WALL OPENING DIMENSIONS WITH AUTOCLAVE MANUFACTURER.
 - PATCH AND REPAIR WALL TO SOFFIT LOCATION ABOVE AS REQUIRED.
 - EXISTING FLOOR SINK TO REMAIN.
 - REMOVE AND REINSTALL EXISTING ACOUSTICAL PANEL CEILING SYSTEM ABOVE AS REQUIRED TO FACILITATE THE INSTALLATION OF THE NEW STEAM SERVICE.



4 MAIN LEVEL FLOOR PLAN - NEW CONSTRUCTION
SCALE: 1/8" = 1'-0"



10 RESILIENT BASE
SCALE: 6" = 1'-0"




7 ENLARGED FLOOR PLAN
SCALE: 1/2" = 1'-0"

NOTE: THE AUTOCLAVES REPRESENTED IN THIS DETAIL ARE FROM PRIMUS (BASIS OF DESIGN).

GENERAL NOTES - PARTITIONS

PLAN SYMBOL LEGEND

- PARTITION TYPE
- STUD DEPTH, NOMINAL: 4B24
- STUD SPACING, INCHES: FH, I
- PARTITION HEIGHT
- CH = FRAMED TO CEILING HEIGHT (REFER TO ROOM FINISH SCHEDULE OR REFLECTED CEILING PLANS)
- +6 = FRAMED TO CEILING HEIGHT PLUS 6 INCHES (OR ANY OTHER SPECIFIED NUMBER)
- FH = FRAMED FULL-HEIGHT (TO OVERHEAD STRUCTURE)
- I = THERMAL OR ACOUSTIC INSULATION
-
- A: NOTE: PLAN SYMBOLS SPECIFY ALL THE INFORMATION LISTED ABOVE - REFER TO PLANS.



5 INTERIOR PARTITION
SCALE: 1 1/2" = 1'-0"

9 WALL OPENINGS
SCALE: 3" = 1'-0"

NOTE: WRAP GYPSUM BOARD THROUGH WALL OPENINGS AT HEAD AND JAMBS AND TRIM WITH MOLDINGS, TYPICAL, THIS SIDE OF WALL ONLY.

DRAWN BY: SS, AC, MV		
REVIEWED BY: SS, AC, MV		
REV.	DESCRIPTION	DATE



PPA # 24-1115

A/E # ...

A118 24-025

SHEET TITLE

SHEET
A1

DATE
IFB 07-02-2025

MECHANICAL LEGEND

PIPING SYMBOLS

—CA—	COMPRESSED AIR
—CHWS—	CHILLED WATER SUPPLY
—CHWR—	CHILLED WATER RETURN
—D—	SPECIALTY EQUIPMENT DRAIN
—DHW—	DOMESTIC HOT WATER
—G—	NATURAL GAS
—HWS—	HEATING WATER SUPPLY
—HWR—	HEATING WATER RETURN
—ICW—	INDUSTRIAL COLD WATER
—IHW—	INDUSTRIAL HOT WATER
—MPS—	MEDIUM PRESSURE STEAM
—MTC—	MEDIUM TEMPERATURE CONDENSATE
—SV—	STEAM VENT
—TW—	TEMPERED WATER

GENERAL MECHANICAL SYMBOLS

	NOTE DESIGNATION
	SECTION REFERENCE
	DETAIL REFERENCE
	EQUIPMENT IDENTIFICATION MARK
	GRILLE OR DIFFUSER MARK BALANCE CFM

DUCT WORK AND SPECIALTIES

	SHEET METAL DUCT (FIRST FIGURE INDICATES FACING SIDE)
	RECTANGULAR DUCT TAKEOFF WITH VOLUME DAMPER
	CONICAL SPIN-IN WITH VOLUME DAMPER
	ACCESS DOOR
	TURNING VANES
	RADIUSED ELBOW
	MOTORIZED DAMPER

PIPE FITTINGS AND SPECIALTIES

	PIPE UP
	PIPE DOWN
	UNION
	CONCENTRIC REDUCER OR INCREASER
	ECCENTRIC REDUCER OR INCREASER
	VALVE IN VERTICAL PIPE
	BALL VALVE
	BUTTERFLY VALVE
	GATE VALVE
	MOTORIZED TWO-WAY VALVE
	MOTORIZED THREE-WAY VALVE
	CHECK VALVE
	BACKFLOW PREVENTOR
	FLOW BALANCE DEVICE
	PRESSURE REDUCING VALVE
	STRAINER
	FLOW SWITCH
	DIFFERENTIAL PRESSURE SENSOR
	MANUAL AIR VENT
	INSTRUMENT TAP / AGENT WELL (PETE'S PLUG)
	THERMOMETER/TEMPERATURE GAUGE
	HOSE BIBB
	THERMOSTAT / SENSOR
	RELIEF VALVE
	PRESSURE GAUGE

OTHER ABBREVIATIONS

AD	ACCESS DOOR
AFF	ABOVE FINISH FLOOR (ELEVATION)
ARCH	ARCHITECT OR ARCHITECTURAL PLANS
BD	BACKDRAFT DAMPER
C	CONDUIT
CO	CLEANOUT
D.I.P.	DUCTILE IRON PIPE
DN	DOWN
(E)	EXISTING
EXH	EXHAUST AIR
FCO	FLOOR CLEANOUT
FD	FIRE DAMPER
FSD	FIRE/SMOKE DAMPER
IJS	IN JOIST SPACE
IWS	IN WALL SPACE
LPG	LIQUIFIED PETROLEUM GAS
OA	OUTSIDE (FRESH) AIR
MECH.	MECHANICAL (CONTRACTOR)
MFR	MANUFACTURER
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
RA	RETURN AIR
SD	SMOKE DAMPER
SM	SHEET METAL
SS	STAINLESS STEEL
VD	VOLUME DAMPER
WCO	WALL CLEANOUT

MISCELLANEOUS EQUIPMENT SCHEDULE

AUTOCLAVE EQ1:
FLOOR MOUNTED, RECESSED STEAM STERILIZER WITH SINGLE VERTICAL SLIDING DOOR, STAINLESS STEEL, FULLY JACKETED 20"x20"x38" CHAMBER, CONFIGURABLE CONTROLS, AND DRAIN WATER COOLING SYSTEM. SEE SPECIFICATIONS SECTION 11 5319 FOR DETAILS.

AUTOCLAVE EQ2:
FLOOR MOUNTED, RECESSED STEAM STERILIZER WITH SINGLE HINGED DOOR, STAINLESS STEEL, FULLY JACKETED 26"x36"x48" CHAMBER, CONFIGURABLE CONTROLS, AND DRAIN WATER COOLING SYSTEM. SEE SPECIFICATIONS SECTION 115319 FOR DETAILS.

STEAM SEPARATOR (SEP-1):
CARBON STEEL BAFFLE TYPE STEAM SEPARATOR. UNIT SHALL BE RATED FOR A MAXIMUM ALLOWABLE TEMPERATURE OF 797 DEGREE F AT 406 PSIG, AND SHALL PRODUCE A PRESSURE DROP OF NO MORE THAN 0.1 PSIG AT A STEAM FLOW RATE OF 265 LBS/HR AT 40 PSIG. PROVIDE IN 1 1/4" SIZE WITH FLANGED OR NPT CONNECTIONS. PROVIDE SPIRAX/SARCO MODEL S5 STEAM SEPARATOR OR APPROVED EQUAL.

PRESSURE REDUCING VALVE (PRV-1):
HIGH FLOW FILTER/REGULATOR COMBINATION FOR COMPRESSED AIR. UNIT SHALL FEATURE POLYCARBONATE BOWL WITH 1/2" NPT CONNECTIONS AND SHALL BE RATED FOR 172 SCFM FOR A 150 PSIG MAX INLET PRESSURE AND 0-140 PSIG OUTLET PRESSURE. FILTER EFFICIENCY SHALL BE 5 MICRONS. PROVIDE ARO MODEL P39344-600 OR APPROVED EQUAL.

CONDENSATE AFTERCOOLER (CAC-1):
304 STAINLESS STEEL UNVENTED HORIZONTAL CONDENSATE COOLING UNIT SUITABLE FOR USE WITH 45 PSIG STEAM CONDENSATE. UNIT SHALL FEATURE SEPARATE STEAM/CONDENSATE COIL AND COLD WATER SHELL TANK. THE UNIT SHALL BE FIT WITH 3/4" CONDENSATE INLET AND 3/4" COLD WATER INLET CONNECTIONS, AND A 3/4" TEMPERED CONDENSATE DRAIN OUTLET AND A 1/2" COLD WATER DRAIN OUTLET. THE UNIT SHALL FEATURE A TEMPERATURE-ACTUATED COLD WATER VALVE WITH TEMPERATURE SENSOR IN THE BOTTOM OF THE HORIZONTAL TANK. PROVIDE WITH THE OPTIONAL FACTORY FLOOR STAND ASSEMBLY. PROVIDE COLTON INDUSTRIES MODEL "CC-VL2" OR APPROVED EQUAL.

SPRING SUPPORTS FOR STEAM RISERS:
PROVIDE SPRING HANGERS AND UNHOUSED SPRING SUPPORTS FOR THE STEAM PIPING TO ACCOMMODATE THERMAL GROWTH. THE REQUIRED HANGERS AND SUPPORTS ARE INDICATED IN THE PLAN DETAILS.

SUBMIT COMPLETE MANUFACTURER'S DATA FOR ALL MISCELLANEOUS EQUIPMENT SCHEDULED ON THIS SHEET AND COMPLY WITH ALL GENERAL SUBMITTAL REQUIREMENTS AS FOUND IN SECTION 23 0000 OF SPECIFICATIONS.

STEAM TRAP SCHEDULE

TRAP	UNIT SERVED	LOCATION	MFR	MODEL	TYPE	PIPE SIZE	ORIFICE SIZE	LBS./ HOUR	PRESS. DIFF.	NOTES
ST 1	SEP-1	-	SPIRAX/SARCO	FT-75	FLOAT & THERM.	3/4"	0.166	970	30 PSID	① STEAM SEPARATOR

① FLOAT AND THERMOSTATIC TRAP WITH STAINLESS STEEL INTERNALS. MAXIMUM OPERATING PRESSURE RATING UP TO 75 PSIG. BODY RATED FOR 125 PSIG AND 450F.


PRESSURE DIFFERENTIAL LISTED ABOVE IS THE MINIMUM PRESSURE DIFFERENTIAL THE TRAP IS EXPECTED TO SEE. POUNDS PER HOUR RATING IS AT THE LISTED PRESSURE DIFFERENTIAL.

LABORATORY EQUIPMENT CONNECTION SCHEDULE

MARK	DESCRIPTION	EXHAUST CONNECTIONS			STEAM CONNECTIONS			CONDENSATE	STEAM VENT	INDUSTRIAL COLD WATER	COMPRESSED AIR	EQUIPMENT DRAIN	REFERENCE DETAIL	NOTES
		QUANTITY	CONNECTION SIZE	AIRFLOW (CFM)	SIZE	LBS/H	PRESSURE RANGE (PSIG)							
EQ1	20x20x38 STEAM STERILIZER	-	-	-	3/4"	65	30-80	-	-	3/4"	1/4"	3/4"	2/M4.0	① SEE SPECIFICATION 11 5319
EQ2	26x36x48 STEAM STERILIZER	-	-	-	1"	200	30-80	-	-	3/4"	1/4"	1"	2/M4.0	① SEE SPECIFICATION 11 5319

GENERAL: REFER TO THE EQUIPMENT SUBMITTAL DRAWINGS FOR LOCATIONS AND DETAILS REGARDING CONNECTIONS TO EQUIPMENT SHOWN IN THIS SCHEDULE. FIELD VERIFY CONNECTION SIZES AND FURNISH NECESSARY ADAPTERS TO MATE TO EQUIPMENT. NOT ALL FIXTURES OR REQUIRED CONNECTIONS ARE INDICATED ON THIS SCHEDULE. SEE PLANS AND MANUFACTURER'S INSTRUCTIONS FOR LOCATIONS OF ALL EQUIPMENT, COMPONENTS AND CONNECTIONS. THE CONTRACTOR IS RESPONSIBLE TO PROCURE SPECIFIC INSTALLATION INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT AND TO INSTALL ALL EQUIPMENT IN COMPLETE ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND IN ACCORDANCE WITH PLANS. THE CONTRACTOR IS RESPONSIBLE TO PROPERLY ACCOMMODATE ANY AND ALL DEVIATIONS FROM INDICATED INSTALLATION METHODS AND MATERIALS WHICH RESULT FROM SUBSTITUTION OF EQUIPMENT TO THE SATISFACTION OF BOTH THE OWNER AND THE EQUIPMENT MANUFACTURER. ALL WORK AND MATERIALS FOR INSTALLATION OF THE EQUIPMENT SHALL CONFORM TO THE PROJECT SPECIFICATIONS.



① PROVIDE ISOLATION VALVES, UNIONS AND REDUCERS AT ALL WATER, AIR AND STEAM PIPING CONNECTIONS. PROVIDE A UNION AT THE DRAIN CONNECTION AND INCREASE DRAIN LINE SIZE BY TWO PIPE SIZES IMMEDIATELY DOWNSTREAM OF THE DRAIN CONNECTION TO THE UNIT. DRAIN PIPING SHALL BE 316 STAINLESS STEEL.



FOR ENLARGED AUTOCLAVE ROOM
PIPING DEMOLITION AND REMODEL
PLANS, SEE DETAIL 1 ON SHEET M2.0
AND DETAILS 1 AND 2 ON SHEET M2.1

FOR PLANS OF THE 2ND AND 3RD
FLOOR PIPE CHASE IN THIS AREA SEE
DETAILS 2 AND 3 ON SHEET M2.0.

1 MAIN FLOOR HVAC & PIPING PLAN – WEST WING



KP KEY PLAN N




MSU-CPDC
MONTANA STATE
UNIVERSITY
BOZEMAN, MONTANA
PHONE: 406.994.5413
FAX: 406.994.5665

**CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT**
BOZEMAN, MONTANA



DRAWN BY: TD&H
REVIEWED BY: DJB

REV.	DESCRIPTION	DATE




PPA#24-1115
TD&H# G25-001

SHEET TITLE
MAIN FLOOR HVAC
& PIPING PLAN



SHEET
M1.1

DATE
IFB 07-02-2025



I:\2025\GPD\G25-001 MSU Chemistry Building Autoclave\Construction Drawings\Mech\G25001-M11_D8.dwg 5/7/2025 9:06 AM




1 MAIN FLOOR ENLARGED PIPING PLAN



2 SECOND FLOOR ENLARGED PIPING PLAN



3 THIRD FLOOR ENLARGED PIPING PLAN



NOTES:

- 1 2" MPS DOWN THROUGH THE BASE OF CHASE ABOVE, AND CONTINUE PIPING TO AUTOCLAVES.
- 2 FOR MEDIUM PRESSURE STEAM AND COMPRESSED AIR PIPING CONTINUATION, SEE ENLARGED PLAN 2, SHEET M2.1.
- 3 CONTINUOUSLY SLOPE PIPING IN DIRECTION OF FLOW.
- 4 2" MPS DOWN FROM PENTHOUSE AND DOWN TO SECOND FLOOR THROUGH THE CHASE. FOR CONTINUATION SEE ENLARGED PLAN 2, THIS SHEET.
- 5 2" MPS DOWN FROM THE 3RD FLOOR.
- 6 HOLD TOP OF PIPE INSULATION TIGHT TO UNDERSIDE OF DUCTWORK TO MAXIMIZE OVERHEAD CLEARANCE.
- 7 2" MPS DOWN THROUGH THE FLOOR OF THE SECOND FLOOR CHASE INTO THE 1ST FLOOR CEILING CAVITY. CORE DRILL AND FIRESTOP CHASE PENETRATION. SEE ENLARGED PLAN 1 THIS SHEET FOR MPS PIPING CONTINUATION.
- 8 STEAM PIPE RIGID MOUNTED SUPPORT AT THE FLOOR PENETRATION, SEE DETAIL 4 ON SHEET M4.0.
- 9 SUPPORT STEAM PIPE FROM THE SECOND FLOOR CEILING WITH SPRING HANGER IMMEDIATELY ADJACENT TO PIPE DROP. SPRING HANGER RATED FOR 54 LBS AND 1.2" DEFLECTION. PROVIDE MASON INDUSTRIES MODEL '30-X-54', OR APPROVED EQUAL.



MSU-CPDC

MONTANA STATE UNIVERSITY
BOZEMAN, MONTANA
PHONE: 406.994.5413
FAX: 406.994.5665

CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT
BOZEMAN, MONTANA



DRAWN BY:	TD&H	
REVIEWED BY:	DJB	
REV.	DESCRIPTION	DATE




PPA#24-1115

TD&H# G25-001

SHEET TITLE
ENLARGED PIPING
PLANS


SHEET
M2.0

DATE
IFB 07-02-2025




I:\2025\GFD\G25-001 MSU Chemistry Building Autoclave\Construction Drawings\Mech\G25001-M20_B8.dwg 5/7/2025 9:06 AM


**FERMENTATION/
AUTOCLAVE
123**



1 ENLARGED AUTOCLAVE DEMOLITION PLAN



**FERMENTATION/
AUTOCLAVE
123**



2 ENLARGED AUTOCLAVE ROOM PIPING PLAN




DEMOLITION NOTES:

- 1 DEMOLISH ALL ICW AND IHW PIPING BACK TO TEE AT THE ROOM ENTRANCE. REMOVE ALL PIPE, VALVES, GAUGES, FITTINGS, ANCHORS, HANGERS, AND SUPPORTS COMPLETE.
- 2 REMOVE ALL DRAIN PIPING, FITTINGS, ANCHORS AND SUPPORTS COMPLETE. PATCH AND REPAIR FLOOR TO SURROUNDING CONDITION.
- 3 REMOVE EXISTING STEAM GENERATOR, AND ALL ASSOCIATED MPS PIPING, HANGERS AND SUPPORTS COMPLETE. REMOVE ANCHORS AND PATCH HOLES TO MATCH SURROUNDING CONDITION.
- 4 REMOVE AUTOCLAVES, STANDS, SUPPORTS, ANCHOR BOLTS AND ALL ASSOCIATED PIPING COMPLETE. PATCH AND REPAIR FLOOR TO MATCH SURROUNDING CONDITION.
- 5 REMOVE EXISTING WATER SOFTENER AND ASSOCIATED WATER AND DRAIN PIPING, COMPLETE. REMOVE ALL ASSOCIATED PIPING AND SUPPORTS.

REMODEL NOTES:

- 1 ROUTE 3/4" STEAM TRAP CONDENSATE TO CONDENSATE AFTERCOOL (CAC-1), SLOPE PIPING CONTINUOUSLY FROM TRAP TO AFTERCOOLER. FOR AFTERCOOL PIPING SEE DETAIL 2, SHEET M4.1.
- 2 FOR AUTOCLAVE PIPING, SEE DETAIL 2, SHEET M4.0.
- 3 1-1/4" VALVED AND CAPPED BRANCH TEES DOWN ON INDUSTRIAL COLD WATER LINE FOR FUTURE WATER SOFTENER CONNECTIONS.
- 4 CONNECT TO EXISTING 1-1/4" ICW WHERE IT ENTERS THE ROOM.
- 5 PIPES IN AT CENTER LINE ELEVATION OF DOUBLE SUPPORT STRUTS. SLEEVE AND SEAL WALL PENETRATIONS. SEE DETAIL 5 ON SHEET M4.0.
- 6 1" TYPE 'L' COPPER AFTERCOOLER DRAIN. ROUTE TO FLOOR SINK. SUPPORT ON HOT DIP GALVANIZED STRUT AT 4 FEET ON CENTER MAXIMUM SPACING AND IMMEDIATELY NEAR FLOOR SINK.
- 7 INDUSTRIAL COLD WATER DOWN ALONG WALL SUPPORTED ON HOT DIP GALVANIZED STRUT SUPPORTS. INSTALL A WATER HAMMER ARRESTOR AT THE TOP OF EACH DROP TO EACH STERILIZER AND TO CAC-1.
- 8 CONNECT TO EXISTING COMPRESSED AIR USING A PRESS FITTING TEE. PRE-ASSEMBLE THE TEE WITH A LENGTH OF PIPE AND ISOLATION VALVE IN ORDER TO MINIMIZE AIR SYSTEM OUTAGE. THE USE OF PRESS FITTINGS IS LIMITED TO THE TEE. INSTALLED IN THE EXISTING LINE.
- 9 PRESSURE GAUGE ASSEMBLY WITH SNUBBER AND ISOLATION BALL VALVE.



KEY PLAN



MSU-CPDC

MONTANA STATE UNIVERSITY
BOZEMAN, MONTANA
PHONE: 406.994.5413
FAX: 406.994.5665

**CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT
BOZEMAN, MONTANA**



DRAWN BY: TD&H
REVIEWED BY: DJB
REV. DESCRIPTION DATE



PPA#24-1115


TD&H# G25-001

SHEET TITLE
ENLARGED
AUTOCLAVE PLANS

SHEET
M2.1


DATE
IFB 07-02-2025

I:\2025\GPD\G25-001 MSU Chemistry Building Autoclave Construction Drawings\Mech\G25001-M30_C6.dwg 5/7/2025 9:06 AM



- NOTES:**
- ① CORE DRILL INTO TOP OF CHASE. 2" MPS DOWN INTO CHASE. INSTALL A SPRING MOUNTED PIPE SUPPORT AT CHASE PENETRATION, SEE DETAIL 4/M4.0. FOR PIPING CONTINUATION, SEE 3/M2.0.
 - ② DROP 2" MPS UNDER SUPPLY AIR DUCT AND OFFSET DOWN INTO CHASE. INSTALL A CAPPED TEE AT THE HIGH POINT FOR A FUTURE VACUUM BREAKER AND THERMOSTATIC AIR VENT, SEE DETAIL 7, SHEET M4.0.
 - ③ SLOPE PIPING UP PARALLEL TO ROOF STRUCTURE.
 - ④ STEAM SWING JOINT.
 - ⑤ CONNECT 2-1/2" MPS BRANCH TO TOP OF EXISTING 4" MPS WITH A 2-1/2" WELD-O-LET. FOR CONNECTION DETAIL, SEE DETAIL 6, SHEET M4.0.

① PENTHOUSE HVAC & PIPING PLAN – WEST WING
 SCALE: 1/4"=1'-0"




MSU-CPDC
 MONTANA STATE UNIVERSITY
 BOZEMAN, MONTANA
 PHONE: 406.994.5413
 FAX: 406.994.5665

**CHEMISTRY ROOM 123
 AUTOCLAVE REPLACEMENT**
 BOZEMAN, MONTANA



DRAWN BY: TD&H
 REVIEWED BY: DJB

REV.	DESCRIPTION	DATE




PPA#24-1115
 TD&H# G25-001


SHEET TITLE
 PENTHOUSE HVAC & PIPING PLAN

SHEET
M3.0


DATE
 IFB 07-02-2025




1 MEDIUM PRESSURE STEAM SUPPLY PIPING
SCALE: NONE




2 AUTOCLAVE PIPING
SCALE: NONE



3 SHAFT PIPE PENETRATION
SCALE: NONE




5 WALL PIPE PENETRATION - STEAM
SCALE: NONE (COMPRESSED AIR PIPING SIMILAR, WITH NO INSULATION)




- ① STEAM TRAP. SEE SCHEDULE FOR TYPE, SIZE AND CAPACITY
- ② STEAM RATED ISOLATION BALL VALVE
- ③ 'Y' STRAINER W/ 20/20 S.S. SCREEN, BLOWDOWN VALVE & HOSE THREAD.
- ④ CHECK VALVE


4 STEAM TRAP ASSEMBLY
SCALE: NONE



6 PENTHOUSE AIR VENT AND VACUUM BREAKER
SCALE: NONE




8 STEAM SEPARATOR PIPING
SCALE: NONE




7 PENTHOUSE STEAM CONNECTION
SCALE: NONE


REV.	DESCRIPTION	DATE



I:\2025\GFD\G25-001 MSU Chemistry Building Autoclave\Construction Drawings\Mech\G25001-M40_C8.dwg 5/7/2025 9:06 AM



1 COMPRESSED AIR TIE-IN
SCALE: NONE



2 CONDENSATE AFTERCOOL PIPING DETAIL
SCALE: NONE

DRAWN BY:	TD&H	
REVIEWED BY:	DJB	
REV.	DESCRIPTION	DATE



PPA#24-1115

TD&H# G25-001

SHEET TITLE
MECHANICAL
DETAILS

SHEET
M4.1

DATE
IFB 07-02-2025

LEGENDS NOTE

THIS IS A STANDARDIZED SYMBOLS LEGEND. ALL SYMBOLS SHOWN MAY OR MAY NOT APPEAR ON OR WITHIN THIS SET OF CONTRACT DOCUMENTS.

GUIDE TO LINE WEIGHTS

	ITEMS SHOWN LIGHT ARE EXISTING AND TO REMAIN
	ITEMS SHOWN BOLD AND SOLID ARE NEW
	ITEMS SHOWN BOLD AND DASHED ARE TO BE REMOVED

ELECTRICAL LEGEND

SYMBOL	DESCRIPTION
\$	SWITCH
\$	SWITCH - 2 POLE
\$ ³	SWITCH - 3 WAY
\$ ⁴	SWITCH - 4 WAY
\$ ^P	SWITCH - WITH PILOT LIGHT
\$ ^{MC}	SWITCH - MOMENTARY CONTACT
\$ ^D	SWITCH - DIMMER
\$ ^K	SWITCH - KEYED
\$ ^F	SWITCH - FAN
\$ ^{OC}	SWITCH - OCCUPANCY SENSOR (SUBSCRIPT INDICATES TYPE)
	PUSH BUTTON
	BELL
	FIRE ALARM CONTROL PANEL
	FIRE ALARM ANNUNCIATOR PANEL
	FIRE ALARM MANUAL PULL STATION
	FIRE ALARM SYNCHRONIZED STROBE
	FIRE ALARM SYNCHRONIZED HORN
	FIRE ALARM SYNCHRONIZED HORN/STROBE
	HEAT DETECTOR
	INFRARED DETECTOR
	SMOKE DETECTOR (SUBSCRIPT DENOTES TYPE)
	SMOKE DETECTOR - DUCT TYPE
	MAGNETIC DOOR HOLDER
	FIRE ALARM SPRINKLER TAMPER SWITCH
	FIRE ALARM SPRINKLER FLOW SWITCH
	FIRE ALARM SMOKE AND FIRE DAMPER
	VIDEO WIRING
	SOUND SYSTEM WIRING
	LOW VOLTAGE WIRING
	VOLUME CONTROL

ELECTRICAL ABBREVIATIONS

AFF	ABOVE FINISHED FLOOR
AC	MOUNTED ABOVE COUNTER
AIC	AMPS INTERRUPTING CURRENT
ATS	AUTOMATIC TRANSFER SWITCH
BMS	BUILDING MANAGEMENT SYSTEM
C	CONDUIT
CLF	CURRENT LIMITING FUSE
EC	ELECTRICAL CONTRACTOR
EX	EXISTING
FACP	FIRE ALARM CONTROL PANEL
G.C.	GENERAL CONTRACTOR
GRD	GROUND
GFI	GROUND FAULT CIRCUIT INTERRUPTER
GFR	GROUND FAULT INTERRUPTER RECEPTACLE
HOA	HANDS-OFF-AUTOMATIC
HP	HORSE POWER
M.C.	MECHANICAL CONTRACTOR
MCC	MOTOR CONTROL CENTER
NL	NEW LOCATION FOR RELOCATED DEVICE
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
PMR	PER MANUFACTURER'S RECOMMENDATIONS
REL	RELOCATE DEVICE TO NEW LOCATION
TEL	TELEPHONE
TFX, XFMR	TRANSFORMER
VFD	VARIABLE FREQUENCY DRIVE
WP	WEATHER PROOF
W\	WITH

ELECTRICAL LEGEND

SYMBOL	DESCRIPTION
	POWER PANEL - 208Y/120 VOLT, 3Ø 4 WIRE
	POWER PANEL - 480Y/277 VOLT, 3Ø 4 WIRE
	MOTOR CONTROL CENTER
	TELEPHONE BOARD
	POWER TRANSFORMER
	DISCONNECT SWITCH
	STARTER - COMBINATION MAGNETIC
	STARTER - MAGNETIC
	FRACTIONAL HP, MOTOR SENTINEL
	VARIABLE FREQUENCY DRIVE
	REMOTE MUSHROOM SWITCH
	BRANCH CIRCUIT CONCEALED IN WALL OR CEILING
	BRANCH CIRCUIT CONCEALED IN OR UNDER FLOOR
	BRANCH CIRCUIT - RUN EXPOSED
	EMPTY CONDUIT - 3/4" UNLESS NOTED OTHERWISE
	CONDUIT STUB OUT
	CONDUIT RUN - NUMBER OF ARROWHEADS INDICATES THE NUMBER OF CIRCUITS REQUIRED.
	SURFACE METAL RACEWAY - MINIMUM .30 SQ. INCH INTERNAL AREA
	METAL WIREWAY - SIZE AS NOTED
	BUS DUCT
	CABLE TRAY OR LADDER
	LIGHT FIXTURE (CEILING OR WALL MOUNT)
	LIGHT FIXTURE (CEILING OR WALL MOUNT)
	LIGHT FIXTURE (CEILING OR WALL MOUNT)
	LIGHT FIXTURE (WALL MOUNT)
	LIGHT FIXTURE (SURFACE)
	LIGHT FIXTURE (SUSPENDED)
	LIGHT FIXTURE (RECESSED)
	LIGHT FIXTURE (SUSPENDED INDIRECT)
	LIGHT FIXTURE (UNDER CABINET OR COUNTER)
	EMERGENCY POWERED LIGHT FIXTURE (NON-SWITCHED)
	EMERGENCY POWERED LIGHT FIXTURE (SWITCHED)
	EXIT LIGHT (CEILING OR WALL MOUNT)
	EXIT LIGHT (CEILING OR WALL MOUNT, SHADED QUARTER INDICATES LETTERED FACE)
	EMERGENCY LIGHT FIXTURE
	POST MOUNTED HID FIXTURE (ARM MOUNTED)
	POST TOP MOUNTED HID FIXTURE (YOKE MOUNTED)
	SIMPLEX CONVENIENCE RECEPTACLE
	DUPLEX CONVENIENCE RECEPTACLE
	DUPLEX CONVENIENCE RECEPTACLE - MOUNTED HORIZONTALLY
	DOUBLE DUPLEX CONVENIENCE RECEPTACLE
	208 VOLT RECEPTACLE NEMA 6-30R UNLESS OTHERWISE NOTED
	CLOCK OUTLET
	THERMOSTAT
	TELEPHONE OUTLET
	DATA OUTLET
	COMBINATION DATA/TELEPHONE OUTLET
	INTERCOM OUTLET
	MULTIOUTLET ASSEMBLY - SIZE AS NOTED W/RECEPTACLE AS NOTED
	MOTOR (M - MOTOR, F - FAN, P - PUMP)
	SPECIAL EQUIPMENT CONNECTION OR OUTLET AS NOTED
	JUNCTION BOX OR J-BOX
	TELE/POWER POLE
	TELEVISION OUTLET
	VIDEO CAMERA
	OCCUPANCY SENSOR (CEILING/WALL MOUNT) (SUBSCRIPT INDICATES TYPE)
	POWER PACK
	TIME CLOCK
	SPEAKER (CEILING OR WALL MOUNT)



MSU-CPDC

MONTANA STATE UNIVERSITY
BOZEMAN, MONTANA
PHONE: 406.994.5413
FAX: 406.994.5665

CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT
BOZEMAN, MONTANA



DRAWN BY: TD&H

REVIEWED BY: BMK

REV. DESCRIPTION DATE



PPA#24-1115

TD&H# G25-001

SHEET TITLE
ELECTRICAL
LEGEND AND
SCHEDULES

SHEET
E0.1

DATE
IFB 07-02-2025

CHEMISTRY ROOM 123
AUTOCLAVE REPLACEMENT
BOZEMAN, MONTANA




DRAWN BY: TD&H

REVIEWED BY: BMK


REV.	DESCRIPTION	DATE

SPECIFIC SHEET NOTES:

- ① DISCONNECT 480V, 200 AMP, 3-PHASE CONNECTION FROM ELECTRIC STEAM BOILER. REMOVE FLEX CONDUIT AND WIRING. MAINTAIN DISCONNECT SWITCH MOUNTED ON WALL. TURN OFF BREAKER IN PANEL 'HEDP' (LOCATED IN ROOM 23 IN BASEMENT) AND LABEL BREAKER AS "SERVES OLD AUTOCLAVE STEAM BOILER DISCONNECT SWITCH IN ROOM 121 - DO NOT TURN ON".
- ② DISCONNECT 120V CONTROL POWER FROM ELECTRIC STEAM BOILER AND REMOVE CONDUIT BACK TO NEAREST JUNCTION BOX. REMOVE WIRING BACK TO PANEL 'LP1H' AND LABEL BREAKER AS SPARE.
- ③ DISCONNECT 120V CONTROL POWER TO AUTOCLAVE, MAINTAIN CIRCUIT FOR REUSE.
- ④ DISCONNECT ADDITIONAL POWER CONNECTION FROM AUTOCLAVE AND REMOVE CONDUIT BACK TO NEAREST JUNCTION BOX. REMOVE WIRING BACK TO PANEL 'LP1H' AND LABEL BREAKER AS SPARE.
- ⑤ REMOVE EXISTING EMERGENCY PUSHBUTTON OFF SWITCHES (EPO'S) AND ALL ASSOCIATED WIRING. PROVIDE STAINLESS STEEL BLANK COVER PLATES IN THEIR PLACE.
- ⑥ DISCONNECT 208V, 125 AMP, 3-PHASE CONNECTION FROM INTEGRAL ELECTRIC STEAM BOILER. REMOVE FLEX CONDUIT AND WIRING. MAINTAIN DISCONNECT SWITCH MOUNTED ON WALL. TURN OFF BREAKER IN PANEL 'LD1W' (LOCATED ACROSS THE HALL) AND LABEL BREAKER AS "SERVES OLD AUTOCLAVE STEAM BOILER DISCONNECT SWITCH IN ROOM 121 - DO NOT TURN ON".
- ⑦ PROVIDE NEW 120V CONTROL POWER CONNECTION TO NEW AUTOCLAVE, USING EXISTING 120V CIRCUIT. PROVIDE 30A-2P NON-FUSED DISCONNECT SWITCH LOCATED NEAR AUTOCLAVE.
- ⑧ PROVIDE CONNECTION TO NEW AUTOCLAVE VACUUM PUMP. CONNECT TO PANEL 'LP1H' VIA 3/4" 12G IN 3/4" CONDUIT. PROVIDE NEW 20A-3P CIRCUIT BREAKER IN PANEL AND RE-ADJUST EXISTING CIRCUIT BREAKERS AS NECESSARY TO ALLOW SPACE FOR NEW 3-POLE BREAKER. PROVIDE 30A-3P NON-FUSED DISCONNECT SWITCH NEAR AUTOCLAVE.



① ENLARGED AUTOCLAVE ELECTRICAL DEMOLITION PLAN
SCALE: 3/4"=1'-0"



② ENLARGED AUTOCLAVE ELECTRICAL REMODEL PLAN
SCALE: 3/4"=1'-0"

